

Weather Louvre Test

448/150

Carried out for
Renson Ventilation NV

Report 104727/2

Compiled by Thomas Costello

8 March 2023



This page is intentionally left blank

Weather Louvre Test

448/150

Carried out for: Renson Ventilation NV
Industriezone 2
Vijerdam
Maalbeekstraat 6
8790
Belgium

Contract: Report 104727/2


Issued by: BSRIA Limited
Old Bracknell Lane West
Bracknell
Berkshire
RG12 7AH
UK

Telephone: +44 (0)1344 465600

Fax: +44 (0)1344 465626

Email: bsria@bsria.co.uk
Website: www.bsria.co.uk

QUALITY ASSURANCE

| Issue | Date | Compiled by: | Approved by: | Signature |
|-------|-------------|-------------------|------------------------------------|--|
| FINAL | 08-Mar-2023 | Thomas Costello | Anthony Collier |  |
| | | Senior Technician | Technical Operations Manager | |

DISCLAIMER

This Document must not be reproduced except in full without the written approval of an executive director of BSRIA. It is only intended to be used within the context described in the text.

This Document has been prepared by BSRIA Limited, with reasonable skill, care and diligence in accordance with BSRIA's Quality Assurance and within the scope of our Terms and Conditions of Business.

This Document is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the Document at its own risk.

CONTENTS

| | | |
|-----|--------------------------------|----|
| 1 | INTRODUCTION..... | 5 |
| 1.1 | Test Item Information | 5 |
| 2 | TEST METHOD | 8 |
| 2.1 | Water Penetration..... | 8 |
| 2.2 | Pressure Drop | 8 |
| 2.3 | Test equipment used..... | 8 |
| 3 | RESULTS | 9 |
| 3.1 | Rainwater Penetration | 9 |
| 3.2 | Coefficient of Entry..... | 10 |
| 3.3 | Coefficient of Discharge | 11 |

FIGURES

| | | |
|----------|--|---|
| Figure 1 | Test item 104727A1 (front) | 6 |
| Figure 2 | Test item 104727A1 (rear) | 6 |
| Figure 3 | Test item 104727A1 (close-up of guard) | 7 |

APPENDICES

| | | |
|-------------|------------------------------|----|
| APPENDIX A: | Manufacturer's Drawing | 12 |
|-------------|------------------------------|----|

1 INTRODUCTION

This report concerns tests conducted on a louvre to determine the Rainwater Penetration and the Pressure Drop versus Airflow Curves, with the associated Coefficient of Entry and Coefficient of Discharge, using the test methods contained within BS EN 13030:2001. It should be noted that BS EN 13030:2001 simply provides a method for testing and rating louvre samples, there are no minimum permitted values or recommendations for louvre performance.

The work was commissioned by Renson Ventilation NV and was carried out at BSRIA North from 11th to 12th January 2023, by Thomas Costello and Samuel Twibill of BSRIA Ltd.

Items received for test

| Test Item | BSRIA ID |
|-----------|----------|
| 448/150 | 104727A1 |


1.1 TEST ITEM INFORMATION

| | |
|-------------------|-----------------------|
| Contract | 104727 |
| Date | 13/1/23 |
| Manufacturer | Renson Ventilation NV |
| Louvre Model | 448/150 |
| Material | Aluminium |
| Painted | No |
| Core Area Height | 975 mm |
| Core Area Width | 973 mm |
| Blade Pack Depth | 150 mm |
| Frame Depth | 155 mm |
| No. of Blades | 6 |
| Blade Pitch | 150 mm |
| Blade Angle | 45° approx. |
| No. of Banks | 1 |
| Guard Type | Insect |
| Guard Spacing | 0 mm |
| Side Channels | No |
| Water Drip Tray | No |
| Blade Orientation | Horizontal |

Note: Weather louvre core area - product of the minimum height H and minimum width W of the front opening in the weather louvre assembly with the louvre blades removed.
Blade Pack Depth refers to the distance from front of first bank to rear of last bank.


Figure 1 Test item 104727A1 (front)**Figure 2 Test item 104727A1 (rear)**

Figure 3 Test item 104727A1 (close-up of guard)



2 TEST METHOD

A schematic representation of the rig used during testing



The test comprises of two parts:

2.1 WATER PENETRATION

The weather louvre is subjected to fan driven wind at a speed of 13 m/s and water sprayed as rainfall at a rate of 75 l/h (+10% / -0%). In addition to the simulated wind and rain, air is drawn through the louvre at various set velocities (0, 0.5, 1.0, 1.5, 2.0, 2.5, 3.0 and 3.5 m/s).

Each test is preceded by a suitable 'pre-test' soak which is typically around 30 minutes. Each test is run until the results become stable, and in any case, for a minimum of 30 minutes.

The penetrated water is collected in the collection duct and is measured and recorded against time elapsed. A range of measurements are taken to give the characteristic curve for the test louvre.

2.2 PRESSURE DROP

For this test, the Aerodynamic Measuring Section (AMS) is separated from the main rig. The louvre is then mounted in the upstream opening of the AMS.

Pressure tapings in the plenum walls of the AMS allow measurement of the static pressure within the plenum during testing. The airflow volume is calculated from the differential pressure at the measuring cones. The plenum has a set of settling screens within to produce even flow through the cones and therefore gives an accurate reading of the total volume.

By adjusting the fan speed, the total airflow through the system varies and therefore changes the pressure on the louvre under test. A range of measurements are taken to give the characteristic curve for the test louvre.

2.3 TEST EQUIPMENT USED

| Test equipment | BSRIA ID | Calibration Expiry Date |
|--------------------------------|----------|-------------------------|
| Rain measuring system | 353 | 19-12-23 |
| Airflow cones | 364 | 18-12-23 |
| Fan | 484 | 19-12-23 |
| Scales (water) | 1599 | 26-05-23 |
| Micromanometer | 1600 | 24-11-23 |
| Micromanometer | 1601 | 24-11-23 |
| Temperature and Pressure Gauge | 1605 | 10-10-23 |
| Flow meter | 1533 | 05-05-23 |
| Water supply measurement | 1749 | 20-12-23 |

3 RESULTS

3.1 RAINWATER PENETRATION

Manufacturer Renson Ventilation NV


Date 12/01/2023

Model 448/150

Contract 104727

| | | | | | |
|--------------------|-----------------|-------|------------------|-------|----------------|
| Simulated Rainfall | 75 (+10% / -0%) | mm/hr | Core Area Height | 973 | mm |
| Wind Speed | 13 (+/-10%) | m/s | Core Area Width | 975 | mm |
| | | | Core Area Area | 0.949 | m ² |

| Ventilation Rate | | Water Flow Rates | | Effectiveness % | Class |
|-----------------------------|-----------------|------------------|-------------------|--------------------|-------|
| Volume m ³ /s | Velocity m/s | Supply l/h | Penetrated l/h | | |
| 0.00 | 0.00 | 97.2 | 2.6 | 96.7 | B |
| 0.47 | 0.50 | 97.2 | 6.8 | 91.3 | C |
| 0.95 | 1.00 | 97.2 | 12.0 | 84.6 | C |
| 1.42 | 1.50 | 97.2 | 21.5 | 72.4 | D |
| 1.90 | 2.00 | 97.2 | 36.7 | 53.0 | D |
| 2.37 | 2.50 | 97.2 | 44.9 | 42.4 | D |
| 2.85 | 3.00 | 97.2 | 49.4 | 37.0 | D |
| 3.32 | 3.50 | 97.2 | 64.0 | 17.9 | D |




3.2 COEFFICIENT OF ENTRY

Manufacturer Renson Ventilation NV
Model 448/150

Date 11/01/2023
Contract 104727

| | | | | | |
|-----------------|-------|-------------------|------------------|-------|----------------|
| Air Temperature | 15.1 | °C | Core Area Height | 973 | mm |
| Barometer | 995.0 | mbar | Core Area Width | 975 | mm |
| Air Density | 1.198 | kg/m ³ | Core Area Area | 0.949 | m ² |

| Louvre p.d. Pa | Louvre Face Velocity | Air Flow Rate | | Coefficient C _e |
|---------------------|----------------------|---------------------------|----------------------------------|-------------------------------|
| | m/s | Test m ³ /s | Theoretical m ³ /s | |
| 10.0 | 1.01 | 0.955 | 3.877 | 0.246 |
| 24.3 | 1.58 | 1.497 | 6.043 | 0.248 |
| 39.9 | 2.05 | 1.945 | 7.744 | 0.251 |
| 57.3 | 2.46 | 2.334 | 9.280 | 0.251 |
| 74.0 | 2.79 | 2.643 | 10.546 | 0.251 |
| 91.2 | 3.09 | 2.936 | 11.707 | 0.251 |
| 108.0 | 3.37 | 3.196 | 12.740 | 0.251 |
| 128.0 | 3.67 | 3.483 | 13.869 | 0.251 |
| 149.0 | 3.95 | 3.743 | 14.964 | 0.250 |
| 169.0 | 4.21 | 3.995 | 15.937 | 0.251 |
| Mean C _e | | | | 0.250 |
| Class | | | | 3 |



A 'trendline' for the above graph would follow $y = 10.865x^{1.9766}$


3.3 COEFFICIENT OF DISCHARGE

Manufacturer Renson Ventilation NV
Model 448/150

Date 11/01/2023
Contract 104727

| | | | | | |
|-----------------|-------|-------------------|------------------|-------|----------------|
| Air Temperature | 15.6 | °C | Core Area Height | 973 | mm |
| Barometer | 995.6 | mbar | Core Area Width | 975 | mm |
| Air Density | 1.196 | kg/m ³ | Core Area Area | 0.949 | m ² |

| Louvre p.d. Pa | Louvre Face Velocity | Air Flow Rate | | Coefficient C _d |
|---------------------|----------------------|---------------------------|----------------------------------|-------------------------------|
| | m/s | Test m ³ /s | Theoretical m ³ /s | |
| 10.0 | 0.87 | 0.830 | 3.879 | 0.214 |
| 31.0 | 1.57 | 1.491 | 6.829 | 0.218 |
| 54.6 | 2.08 | 1.971 | 9.063 | 0.217 |
| 76.0 | 2.45 | 2.321 | 10.693 | 0.217 |
| 97.4 | 2.79 | 2.644 | 12.105 | 0.218 |
| 121.0 | 3.10 | 2.937 | 13.492 | 0.218 |
| 148.0 | 3.37 | 3.198 | 14.922 | 0.214 |
| 169.0 | 3.62 | 3.439 | 15.946 | 0.216 |
| 189.0 | 3.88 | 3.677 | 16.863 | 0.218 |
| 217.0 | 4.15 | 3.933 | 18.069 | 0.218 |
| Mean C _d | | | | 0.217 |
| Class | | | | 3 |



A 'trendline' for the above graph would follow $y = 14.266x^{1.9895}$

APPENDIX A: MANUFACTURER’S DRAWING

